



AmulFed Dairy

A UNIT OF GUJARAT CO-OPERATIVE MILK MARKETING FEDERATION LIMITED

(PREVIOUSLY KNOWN AS MOTHER DAIRY, GANDHINAGAR)

AFD: CIVIL: INQ: 20231101

November 02, 2023

To,

Sub: - Inquiry for Civil work for Endura Tiles Flooring for Line No. 1 to 4 at Pouch Crate washer area at AFDG.

We invite your most competitive offer, quoting your lowest rate and shortest execution period for item mentioned as under. Your offer must be sent in sealed reply envelope attached herewith by registered post/courier or by person. Mention, "Civil work for Endura Tiles Flooring for Line No. 1 to 4 at Pouch Crate washer area at AmulFed Dairy, Gandhinagar." on top of the offer reply envelope.

Detailed Technical Specification & Schedule of Quantities as per Enclosed Annexure: - I

Last date of receipt of Quotation: 18th November 2023.

➤ General Terms & Conditions.

1. Contractor has to quote rates considering work is to be carried out at AmulFed Dairy, Gandhinagar.
2. Your rates should be including of all material cost, labour cost, octroi, loading, unloading at AmulFed Dairy.
3. The Contractor will have to bring his own tools, tackles, ladders, accessories, scaffolding etc.
4. Specify Tax Condition. GST will be applicable or not. If tax condition is not specified your rates shall be considered as inclusive of all taxes.
5. **It is advisable to visit the site before quoting your rates.**
6. If work is to be carried out in emergency basis or during Shutdown period, contractor should Carry out work on emergency basis, night work shall be permitted under such Intervention to meet production schedule.
7. Payment terms: 30 days after submission of bill based on JMS / JMR.
8. Quantity indicated here is estimated; it may vary on either side however payment shall be made as per the actual work executed at site based on JMS / JMR.
9. To the extent possible extra item shall be avoided. If however is necessary done as per site Condition & is not envisaged in the current SOR we shall fix the rate base on competitive Offers from the market which shall be binding to the contractor. Contractor should inform well in advance about the requirement of the extra item to us to get enough time to collect

M. C. Mehta

Comparative offers.

November 02, 2023

AFD: CIVIL: INQ: 20231101

10. All the legal/ administrative records like muster roll, salary register, labour license, PF, ESI etc. to be maintained & submitted as and when required and contractor is responsible for labour laws and rules/ regulations etc.
11. Cleaning of site must be required after day-to-day work.
12. Your workmen should wear the identity card of your company while executing jobs at AFD, Gandhinagar.
13. In case, any of your workmen get injured due to Accident, while working within premises of AFD, or any damage to our equipment or property has taken place due to your workmen, you will repay the damages/losses.
14. We are ISO 9001:2004 QMS (Quality Management System), ISO 14001:2004 (Environmental Management System) ISO 22000:2005 FSS (Food & Safety System) certified unit. We expect you to follow eco-friendly process in your Company such as waste minimization, reduction in air pollution, waster pollution and soil Contamination etc.
15. Chewing pan masala, tobacco & smoking is strictly prohibited in AFD premises and if any person is catch then penalty would be Rs. 5000/- each.
16. You shall be working in running factory and ensure that the day to day operations of the factory are not hampered in any way due to your activities. Any damages occurred by you shall be recovered. Proper barricading of the work area should be done to prevent dust dirt etc. in the environment.
17. Water and Electricity will be provided by AFD free of cost.
18. Safety is the utmost priority inside the premises & Contractor must ensure your team to follows all the safety norms (like use of PPE Personal Protective Equipments, fall protection, secured & safe staging, scaffolding etc.) A safety hand book shall be provided for ready reference if required. If any person not following the safety rules and regulations penalty would be Rs. 1000/- from the Bill.
19. Contractor shall indemnify AFD from any kind of losses due to the activities of the contractor.
20. All Samples to be got approved before fixing.
21. All works executed must remain under one year defect liability period pertaining to defects due to bad workmanship, use of sub-standard materials, improper methods of application etc and must be attended free of charge during this period.

AmulFed Dairy shall not accept the offer, received later than the date mentioned above.

Yours faithfully,

M. C. M = H

For, AmulFed Dairy, Gandhinagar.

Annexure : I

Technical Specification and Scope of work for Civil work for Endura Tiles Flooring for Line No. 1 to 4 at Pouch Crate washer area at AFDG.

It. No.	Item Description	UOM	Qty.	Rate	Amount
1	Providing & laying non skid Endura (Acid-Alkali resistant) INDUSTRIAL TILES ENDURA / PAVIT make 20 mm thick manufactured by M/s H & R Johnson (India) or Pavit Ceramics or equivalent for industrial flooring in cement mortar 1 : 4 (1 cement : 4 coarse sand) 35-40mm thick bedding including chemical admixer, keeping the joints 5 mm wide and 10-12mm depth around for epoxy grouting of approved make, line level, necessary curing, cleaning after laying etc. complete as directed.	Sqmt	470.00		
2	Removing any type of existing flooring & dado including removing debries outside the premises as & where directed.	Sqmt	500.00		
3	Providing & laying 50 mm thick IPS - cement concrete pavement with 1 : 2 : 4 (1 cement : 2 coarse sand : 4 aggregate 20 mm. nominal size), including giving broom finish with a floating coat of 1:1:2 cement mortar using grit, curing etc. complete as directed.	Sqmt	460.00		
4	Dismantling PCC /IPS in floor as per instructions including finishing the broken surface to match with the surroundings. Disposing debris/ muck as directed within the site or as directed by Eng. Incharge etc. complete as directed.	Cmt	30.00		
5	Providing Readymade Kota stone coving at junctions of walls and flooring with Cement Concrete (1:2:4) using stone aggregates and finishing the same with neat cement, curing, polishing etc. complete as per detail and directed.	Rmt	100.00		

M. C. Melhi

Annexure : I

Technical Specification and Scope of work for Civil work for Endura Tiles Flooring for Line No. 1 to 4 at Pouch Crate washer area at AFDG.

It. No.	Item Description	UOM	Qty.	Rate	Amount
6	Providing and laying in position ceramic/Glazed tiles for flooring, skirting and wall dado of approved make and colour for first quality of any size as per design fixing in cement slurry over 12-15mm thick cement mortar bedding (1 : 4) and laid to proper slope and level. Joints shall be filled with specified colour pigment to match the shade of tiles including curing and cleaning with mild auxalic acid etc. complete as directed.	Sqmt	30.00		
7	Removing any type of plaster including removing debris outside the premises as & where directed.	Sqmt	50.00		
8	Providing 20 to 25 mm thick water proof cement plaster in double coat on any surface at all heights, finish even and smooth in CM 1 : 4 including providing and mixing water proofing material such as pidilite or equivalent as approved by engineer in cement mortar as proportion recommended by manufacture.	Sqmt	50.00		
9	Dismantling brick work including removing debries within / outside the premises as & where directed.	Cmt	5.00		
10	Tractor Trips from one site to another site including loading of any material, debries, earth, and unloading the same within AFD premised or outside without spillage of material and tyre marks on road. Spillage or marks if observed during transportation of material same shall be cleanded any contractor at his own cost and risk.	Nos.	20.00		
11	Supply of Skilled mason	Nos	5.00		
12	Supply of Un Skilled Helper	Nos	10.00		
	Total Amount	Rs.			
	GST @ 18%	Rs.			
	Total Amount with GST	Rs.			

M. C. Mehta